CONCEPT DESIGN FEATURES

Main Reserve Frontage

1 - Provide widened feature paved threshold to existing pathway entry to North Harbour Reserve open space including sandstone flagging, timber bollard, feature garden landscape treatment;

2 - Proposed hedge planting to delineate park frontage, provide barrier to road and soften amenities building and ramp with Buxus species, to be maintained at 0.6m high;

Amenities & Playground

Reconfiguartion of park and playground entry area including:

3 - Widen pedestrian ramp access, new repositioned bike parking, bin and drinking fountain facilities;

- Widen existing access stairs (2.0m wide) with new handrail, sandstone block edging and repositioned seat;

4 - Proposed feature paved gathering space (sandstone flagging/coloured concrete) adjacent playground entry. Upgrade and reposition community notice board and way-finding signage;

5 -Replace and reposition existing picnic table setting under fig tree;

6 - Proposed sandstone block edging to existing native garden area; Additional native garden beds to surrounds of accessible ramp & embankment area adjacent stair access;

7 - Upgrade existing access pathways (2.0m wide) to foreshore with coloured concrete,

Playground

8 - Larger paved threshold to highlight playground entry from reserve, new bin station set into existing fenceline;

9 - Realigned pathway from playground to foreshore;

Basketball / Youth Space

10 - Large feature sandstone sitting rocks set in synthetic turf area;

11 - Feature curved bench seats, parkour elements, timber stage set in rubber surfacing;

Nature Play Zone

12 - Nature-based play area inspired by local fauna with ramped access, mulch softfall and sandstone seat surrounds;

13 - Play equipment offering climbing timber and rope elements for varying ages & abilities;
- Sensory play with timber musical elements, carved totem poles and sandstone art

Picnic Areas

14 - Reconfigure and upgrade existing picnic facilities including new table settings, backed seats, accessible BBQ (double-hotplate), bin station, sandstone seat walling;

Manly Scenic Walkway Southern Entry

15 - New handrail and minor repair work to existing stair access. Upgrade existing stormwater pit to capture water runoff from roadway;

16 - Reposition existing seat for views

17 - Incorporate new drinking fountain at path junction;

18 - Proposed native shade tree plantings within the reserve;

northern beaches council

North Harbour Reserve Landscape Improvements Plan

Sheet 03 - Area 2 Nature Play & Picnicing

July 2020