

- 1. INSTALL 2 KERB RAMPS TO AUGN ACROSS TULLAMORE AVE. REINSTALL WESTERN KERB RAMP TO MATCH INTO EXISTING FOOTPATH, ON EASTERN SIDE MATCH 1.5M FOOTPATH TO BACK OF KERB
- 2. CONSTRUCT A 1.5M FOOTPATH 1M FROM PROPERTY BOUNDARY, TRANSITION FOOTPATH TO 1.7M FROM PROPERTY BOUNDARY AND MATCH INTO DRIVEWAY RETAINING WALL IN FRONT OF PROPERTY

- NO. 8 AND 10.

 TRANSITION FOOTPATH 1.7M FROM BOUNDARY TO 0.6M FROM BOUNDARY FROM THE START OF BOUNDARY NO. 27 FOR APPROX. 5M LONG, MATCH INTO PROTRUDING BOUNDARY IF NEEDED IN FRONT OF PROPERTY NO. 18.

 CONTINUE CONSTRUCTION OF 1.5M FOOTPATH 0.6M FROM BOUNDARY, IN FRONT OF PROPERTY NO. 22 REMOVE TREE AND MATCH INTO PROPERTY PLANT AREA IF NEEDED, MAJOR ROOT AS NOTED ON THE PLANS WILL REQUIRE FOOTPATH TO BE RAISED WITH SAND AND 0.6M BATTER AND RETURN ON EITHER SIDE OF FOOTPATH IN FRONT OF PROPERTY NO. 22.

 INSTALL A 1.2M WINGLESS KERB RAMP AS PER COUNCIL STANDARD ON THE CORNER OF RATHOWEN AND KILKENNY, INSTALL IN BETWEEN TREE AND POWER POLE STAYING CLOSE TO POWER POLE
- AS SHOWN, REMOVE PLANT,

- AS SHOWN, REMOVE PLANT.

 INSTALL A 1.5M KERB RAMP TO AUGN WITH WINGLESS KERB RAMP ACROSS KILKENNY AVE. CONSTRUCT 1.5M FOOTPATH 1.2M FROM BACK OF KERB AND CONTINUE AS SHOWN.

 INSTALL A BOARDING SLAB AND TACTILE IN FRONT OF PROPERTY NO. 30 AS PER COUNCIL STANDARD NEXT TO EXISTING J STEM. NO BUS ZONE SIGNS TO BE INCLUDED.

 INSTALL 2 KERB RAMPS TO ALIGN ACROSS CARLOW CRES AND CONTINUE 1.5M FOOTPATH 1.2M FROM BACK OF KERB.

 INSTALL 2 KERB RAMPS TO ALIGN ACROSS CARLOW CRES. CONTINUE 1.5M FOOTPATH 1.2M FROM BACK OF KERB.

 INSTALL 2 KERB RAMPS TO ALIGN ACROSS CARLOW CRES. CONTINUE 1.5M FOOTPATH 1.2M FROM BACK OF KERB.

 INSTALL 2 KERB RAMPS TO ALIGN ACROSS CARLOW CRES. CONTINUE 1.5M FOOTPATH 1.2M FROM BACK OF KERB.

 INSTALL 2 KERB RAMPS TO ALIGN ACROSS CARLOW CRES. CONTINUE 1.5M FOOTPATH 1.2M FROM BACK OF KERB.

 INSTALL 2 KERB RAMPS TO ALIGN ACROSS CARLOW CRES. CONTINUE 1.5M FOOTPATH 1.2M FROM BACK OF KERB.

 INSTALL 2 KERB RAMPS TO ALIGN ACROSS CARLOW CRES. CONTINUE 1.5M FOOTPATH 1.2M FROM BACK OF KERB TO ALIGN ACROSS RATHOWEN ST AS SHOWN.

 INSTALL A KERB RAMP TO ALIGN ACROSS RATHOWEN ST AS SHOWN.

 IS CONSTRUCT A 1.5M FOOTPATH 1.2M FROM BACK OF KERB TO MATCH INTO EXISTING FOOTPATH AS SHOWN. REMOVE TREE AND ROOTS AND RETURF EXCAVATED AREA IN FRONT OF NO. 31.

 INSTALL A KERB RAMP TO ALIGN ACROSS RATHOWEN ST AS SHOWN.

 IS CONSTRUCT A 1.5M FOOTPATH 1.2M FROM BACK OF KERB TO MATCH INTO EXISTING FOOTPATH AS SHOWN. REMOVE TREE AND ROOTS AND RETURF EXCAVATED AREA IN FRONT OF NO. 31.

 INSTALL A KERB RAMP TO ALIGN ACROSS RATHOWEN ST AS SHOWN.

 INSTALL A KERB RAMP TO ALIGN ACROSS RATHOWEN ST AS SHOWN.

 INSTALL A KERB RAMP TO ALIGN ACROSS RATHOWEN ST AS SHOWN.

 INSTALL A KERB RAMP TO ALIGN ACROSS RATHOWEN ST AS SHOWN.

 INSTALL A KERB RAMP TO ALIGN ACROSS RATHOWEN ST AS SHOWN.

 INSTALL A KERB RAMP TO ALIGN ACROSS RATHOWEN ST AS SHOWN.

 INSTALL A KERB RAMP TO ALIGN ACROSS RATHOWEN ST AS SHOWN.

 INSTALL A KERB RAMP TO ALIGN ACROSS RATHOWEN ST AS SHOWN.

 INSTALL A KERB RAMP TO ALIGN ACROSS RATHOWEN ST AS SHOWN.

 INSTALL A KERB RAMP TO

- 21, MATCH FOOTPATH INTO TELSTRA, PMG, HYDRANT AND SV LID'S AS SHOWN.
- 22. CUT BACK OVERHANGING BRANCHES AS PER COUNCIL'S ARBORIST DIRECTION. MAINTAIN A 3M DIAMETER OF NO EXCAVATION AROUND TREE AS PER COUNCIL ARBORIST DIRECTION.

- 23. INSTALL CONCRETE FOOTPATH WITH TRIP STOP JONI'S NEAR TREES. TRIM ROOTS AS PER COUNCIL'S ARBORIST DIRECTION.

 24. BATTER AND RETURF A MIN 0.6M ALONG FOOTPATH EDGE.

 25. THE POSITION OF TREES, SERVICES PTS, POLES, MARKER POSTS, SIGNS, ETC ARE INDICATIVE ONLY.

 26. IT IS THE RESPONSIBILITY OF THE CONTRACTOR PRIOR TO ANY DEMOLITION, EXCAVATION OR CONSTRUCTION ACTIVITY ON OR ADJACENT TO THE SITE TO OBTAIN UPDATED SERVICES DIAGRAMS THROUGH A DIAL—BEFORE—YOU—DIG SEARCH AND PHYSICAL SEARCH TO ESTABLISH AND CONFIRM THE EXACT LOCATION/S AND DEPTH/S OF ALL UNDERGROUND SERVICES, PROR TO COMMENCEMENT.

LEGEND







NEW FOOTPATH 1.5M WIDE UNO ACROSS INDUSTRIAL DWY ALIGNMENT 180MM THICK PLAIN CONCRETE 25MPa SL82 REO 30MM COVER, COVE FINISH

NEW CONCRETE PRAM RAMP, COLOUR - DARK TERRACOTTA 25MPa WINGS 500MM WIDE **COVE FINISH**

SUMMARY OF WORK


- CONSTRUCTION OF APPROX. 343M OF CONCRETE FOOTPATH 1.5M WIDE (APPROX. 515M²)
- BATTER AND RETURF SIDES AS
- REQUIRED(APPROX. 412M2)
- INSTALL 10 KERB RAMPS
- RELOCATE 1 J STEM AND INSTALL 2 BUS ZONE
- INSTALL 2 BUS STANDS WITH TACTILES
- REMOVE 2 TREES
- TRIM OVERHANGING BRANCHES FROM FOOTPATH
- REMOVE 1 PLANT
- RELOCATE 3 SIGN POSTS



_AYOUT PLAN 1 northern RATHOWEN PARADE

KILLARNY HEIGHTS
FOOTPATH CONCEPT PLAN ISSUED FOR CONSTRUCTION

DRAWING NO. TCI-RATHOWEN PARADE FOOTPATH-0001-CONCEPT



- INSTALL 2 KERB RAMPS TO ALIGN ACROSS TULLAMORE AVE, REINSTALL WESTERN KERB RAMP TO MATCH INTO EXISTING FOOTPATH, ON EASTERN SIDE MATCH 1.5M FOOTPATH TO BACK OF KERB
- CAMP.

 CONSTRUCT A 1.5M FOOTPATH 1M FROM PROPERTY BOUNDARY. TRANSITION FOOTPATH TO 1.7M FROM PROPERTY BOUNDARY AND MATCH INTO DRIVEWAY RETAINING WALL IN FRONT OF PROPERTY NO. 8 AND 10.

 TRANSITION FOOTPATH 1.7M FROM BOUNDARY TO 0.6M FROM BOUNDARY FROM THE START OF BOUNDARY NO. 27 FOR APPROX. 6M LONG. MATCH INTO PROTRUCING BOUNDARY IF NEEDED IN
- 3. TRANSITION FOOTPATH 1.7M FROM BOUNDARY TO 0.6M FROM BOUNDARY FROM THE START OF BOUNDARY NO. 27 FOR APPROX, 6M LONG, MATCH INTO PROTRUDING BOUNDARY IF NEEDED IN FRONT OF PROPERTY NO. 18.

 4. CONTINUE CONSTRUCTION OF 1.5M FOOTPATH 0.6M FROM BOUNDARY. IN FRONT OF PROPERTY NO. 22 REMOVE TREE AND MATCH INTO PROPERTY PLANT AREA IF NEEDED.

 5. MAJOR ROOT AS NOTED ON THE PLANS WILL REQUIRE FOOTPATH TO BE RASED WITH SAND AND 0.6M BATTER AND RETURE ON EITHER SIDE OF FOOTPATH IN FRONT OF PROPERTY NO. 22.

 6. INSTALL A 1.2M WINGLESS KERB RAMP AS PER COUNCIL STANDARD ON THE CORNER OF RATHOWEN AND KILKENNY. INSTALL IN BETWEEN TREE AND POWER POLE AS SHOWN. REMOVE PLANT.

 7. INSTALL A 1.5M KERB RAMP TO AUGN WITH WINGLESS KERB RAMP ACROSS KILKENNY AVE. CONSTRUCT 1.5M FOOTPATH 1.2M FROM BACK OF KERB AND CONTINUE AS SHOWN.

 8. INSTALL A BOARDING SLAB AND TACTILE IN FRONT OF PROPERTY NO. 30 AS PER COUNCIL STANDARD NEXT TO EXISTING J STEM. NO BUS ZONE SIGNS TO BE INCLUDED.

 9. INSTALL 2 KERB RAMPS TO AUGN ACROSS CARLOW CRES AND CONTINUE 1.5M FOOTPATH 1.2M FROM BACK OF KERB. MAINTAIN CLEARANCE OF POWER POLE.

 10. INSTALL 2 KERB RAMPS TO AUGN ACROSS CARLOW CRES. CONTINUE 1.5M FOOTPATH 1.2M FROM BACK OF KERB. MAINTAIN CLEARANCE OF POWER POLE.

 11. RELOCATE BUS J STEM AS SHOWN AND INSTALL BOARDING SLAB AND TACTILES IN FRONT OF PROPERTY NO. 40 AS PER COUNCIL STANDARD. INCLIDE A BUS ZONE SIGN 14M BEFORE J STEM MAINTAINING 10M FROM INTERSECTION, AND A BUS ZONE SIGN 5.6 M BERIND J STEM AS SHOWN.

 12. INSTALL A KERB RAMP 1.2M AFTER J STEM IN FRONT OF PROPERTY NO.42 AND INSTALL ADDITIONAL KERB RAMP TO AUGN ACROSS RATHOWEN ST AS SHOWN.

 13. CONSTRUCT A 1.5M FOOTPATH 1.2M FROM BACK OF KERB TO MATCH INTO EXISTING FOOTPATH AS SHOWN. REMOVE TREE AND ROOTS AND RETURF EXCAVATED AREA IN FRONT OF NO. 31.

 14. RELOCATE SIGN POST TO 0.6M FROM TO PROPERTY NO.42, AB AND 40.

 27. MATCH FOOTPATH INTO TELSTRA, PMG, HYDRANT AND SV LID'S AS SHOWN.

- 21. MATCH FOOTPATH INTO TELSTRA, PMG, HYDRANT AND SV LID'S AS SHOWN.

- 22. CUT BACK OVERHANDING BRANCHES AS PER COUNCIL'S ARBORIST DIRECTION. MAINTAIN A 3M DIAMETER OF NO EXCAVATION AROUND TREE AS PER COUNCIL ARBORIST DIRECTION.


 23. INSTALL CONCRETE FOOTPATH WITH TRIP STOP JOINTS NEAR TREES. TRIM ROOTS AS PER COUNCIL'S ARBORIST DIRECTION.

 24. BATTER AND RETURE A MIN 0.6M ALONG FOOTPATH EDGE.

 25. THE POSITION OF TREES, SERVICES BY TS, POLES, MARKER POSTS, SIGNS, ETC ARE INDICATIVE ONLY.

 26. IT IS THE RESPONSIBILITY OF THE CONTRACTOR PRIOR TO ANY DEMOLITION, EXCAVATION OR CONSTRUCTION ACTIVITY ON OR ADJACENT TO THE SITE TO OBTAIN UPDATED SERVICES DIAGRAMS THROUGH A DIAL-BEFORE-YOU-DIG SEARCH AND PHYSICAL SEARCH TO ESTABLISH AND CONFIRM THE EXACT LOCATION/S AND DEPTH/S OF ALL UNDERGROUND SERVICES, PRIOR TO

LEGEND









NEW CONCRETE PRAM RAMP, COLOUR - DARK TERRACOTTA 25MPa WINGS 500MM WIDE **COVE FINISH**


SUMMARY OF WORK

- CONSTRUCTION OF APPROX. 343M OF CONCRETE FOOTPATH 1.5M WIDE (APPROX. 515M²)
- BATTER AND RETURF SIDES AS
- REQUIRED(APPROX. 412M2) INSTALL 10 KERB RAMPS
- RELOCATE 1 J STEM AND INSTALL 2 BUS ZONE
- INSTALL 2 BUS STANDS WITH TACTILES
- REMOVE 2 TREES
- TRIM OVERHANGING BRANCHES FROM FOOTPATH
- REMOVE 1 PLANT
- RELOCATE 3 SIGN POSTS



LAYOUT PLAN 2 northern RATHOWEN PARADE beaches KILLARNEY HEIGHTS FOOTPATH CONCEPT PLAN ISSUED FOR CONSTRUCTION

DRAWING NO. TCI-RATHOWEN PARADE FOOTPATH-0002-CONCEPT



- 1. INSTALL 2 KERB RAMPS TO AUGN ACROSS TULLAMORE AVE, REINSTALL WESTERN KERB RAMP TO MATCH INTO EXISTING FOOTPATH, ON EASTERN SIDE MATCH 1.5M FOOTPATH TO BACK OF KERB
- RAMP.
 2. CONSTRUCT A 1.5M FOOTPATH 1M FROM PROPERTY BOUNDARY. TRANSITION FOOTPATH TO 1.7M FROM PROPERTY BOUNDARY AND MATCH INTO DRIVEWAY RETAINING WALL IN FRONT OF PROPERTY
- NO. 8 AND 10.
 3. TRANSITION FOOTPATH 1.7M FROM BOUNDARY TO 0.6M FROM BOUNDARY FROM THE START OF BOUNDARY NO. 27 FOR APPROX. 6M LONG, MATCH INTO PROTRUDING BOUNDARY IF NEEDED IN FRONT OF PROPERTY NO. 18.
- FRONT OF PROPERTY NO. 18.

 CONTINUE CONSTRUCTION OF 1.5M FOOTPATH 0.6M FROM BOUNDARY, IN FRONT OF PROPERTY NO. 22 REMOVE TREE AND MATCH INTO PROPERTY PLANT AREA IF NEEDED.

 MAJOR ROOT AS NOTED ON THE PLANS WILL REQUIRE FOOTPATH TO BE RASED WITH SAND AND 0.6M BATTER AND RETURN ON EITHER SIDE OF FOOTPATH IN FRONT OF PROPERTY NO. 22.

 INSTALL A 1.2M WINGLESS KERB RAMP AS PER COUNCL STANDARD ON THE CORNER OF RATHOWEN AND KILKENNY, INSTALL IN BETWEEN TREE AND POWER POLE STAYING CLOSE TO POWER POLE
- AS SHOWN, REMOVE PLANT,

- AS SHOWN. REMOVE PLANT.

 NSTALL A 1.5M KERB RAMP TO AUGN WITH WINGLESS KERB RAMP ACROSS KILKENNY AVE. CONSTRUCT 1.5M FO OTPATH 1.2M FROM BACK OF KERB AND CONTINUE AS SHOWN.

 NSTALL A BOARDING SLAB AND TACTILE IN FRONT OF PROPERTY NO. 30 AS PER COUNCIL STANDARD NEXT TO EXISTING J STEM. NO BUS ZONE SIGNS TO BE INCLUDED.

 INSTALL 2 KERB RAMPS TO AUGN ACROSS CARLOW CRES AND CONTINUE 1.5M FOOTPATH 1.2M FROM BACK OF KERB.

 INSTALL 2 KERB RAMPS TO AUGN ACROSS CARLOW CRES. CONTINUE 1.5M FOOTPATH 1.2M FROM BACK OF KERB. MAINTAIN CLEARANCE OF POWER POLE.

 INSTALL 2 KERB RAMPS TO AUGN ACROSS CARLOW CRES. CONTINUE 1.5M FOOTPATH 1.2M FROM BACK OF KERB. MAINTAIN CLEARANCE OF POWER POLE.

 INSTALL 2 KERB RAMPS TO AUGN ACROSS CARLOW CRES. CONTINUE 1.5M FOOTPATH 1.2M FROM BACK OF KERB. MAINTAIN CLEARANCE OF POWER POLE.

 INSTALL 2 KERB RAMP TO AUGN ACROSS CARLOW CRES. CONTINUE 1.5M FOOTPATH 1.2M FROM DISTALL BOARDING SLAB AND TACTILES IN FRONT OF PROPERTY NO. 40 AS PER COUNCIL STANDARD. INCLIDE A BUS ZONE SIGN 14M BEFORE J STEM MAINTAINING TOM FROM INTERSECTION, AND A BUS ZONE SIGN 5.5M BEHIND J STEM AS SHOWN.

 IS CONSTRUCT A 1.5M FOOTPATH 1.2M FROM BACK OF KERB TO MATCH INTO EXISTING FOOTPATH AS SHOWN, REMOVE TREE AND ROOTS AND RETURE EXCAVATED AREA IN FRONT OF NO. 31.

 RELOCATE SIGN POST TO 0.6M FROM KERB IN FRONT OF PROPERTY NO. 24, 28 AND 40.

 MAINTAINING TOM FROM THE STRAP PAGE HOR AND AND AND AND AND AS SHOWN.

- 14. RELOCATE SIGN POST TO 0.5M FROM KERB IN FRONT OF PROPERTY NO. 24, 28 AND 40.
 21. MATCH FOOTPATH INTO TELSTRA, PMG, HYDRANT AND SV LID'S AS SHOWN.
 22. CUT BACK OVERHANGING BRANCHES AS PER COUNCIL'S ARBORIST DIRECTION. MAINTAIN A 3M DIAMETER OF NO EXCAVATION AROUND TREE AS PER COUNCIL ARBORIST DIRECTION.
 23. INSTALL CONCRETE FOOTPATH WITH TRIP STOP JOINTS NEAR TREES. TRIM ROOTS AS PER COUNCIL'S ARBORIST DIRECTION.
 24. BATTER AND RETURE A MIN 0.5M ALONG FOOTPATH EDGE.
 25. THE POSITION OF TREES, SERVICES PTS, POLES, MARKER POSTS, SIGNS, ETC ARE INDICATIVE ONLY.
 26. IT IS THE RESPONSIBILITY OF THE CONTRACTOR PRIOR TO ANY DEMOLITION, EXCAVATION OR CONSTRUCTION ACTIVITY ON OR ADJACENT TO THE SITE TO OBTAIN UPDATED SERVICES DIAGRAMS THROUGH A DIAL—BEFORE—YOU—DIG SEARCH AND PHYSICAL SEARCH TO ESTABLISH AND CONFIRM THE EXACT LOCATION/S AND DEPTH/S OF ALL UNDERGROUND SERVICES, PRIOR TO COMMENCEMENT.

LEGEND









NEW CONCRETE PRAM RAMP, COLOUR - DARK TERRACOTTA 25MPa WINGS 500MM WIDE **COVE FINISH**

SUMMARY OF WORK

- CONSTRUCTION OF APPROX. 343M OF CONCRETE FOOTPATH 1.5M WIDE (APPROX. 515M²)
- BATTER AND RETURF SIDES AS
- REQUIRED(APPROX. 412M2) INSTALL 10 KERB RAMPS
- RELOCATE 1 J STEM AND INSTALL 2 BUS ZONE
- INSTALL 2 BUS STANDS WITH TACTILES
- REMOVE 2 TREES
- TRIM OVERHANGING BRANCHES FROM FOOTPATH
- REMOVE 1 PLANT
- RELOCATE 3 SIGN POSTS



LAYOUT PLAN 3 northern RATHOWEN PARADE beaches council ISSUED FOR CONSTRUCTION

KILLARNEY HEIGHTS FOOTPATH CONCEPT PLAN

DRAWING NO. TCI-RATHOWEN PARADE FOOTPATH-0003-CONCEPT

