





- THE POSITION OF SERVICES SHOWN ON THE DRAWING ARE INDICATIVE ONLY AND HAVE BEEN PLOTTED FROM PLANS SUPPLIED BY THE RELEVANT UTILITY AUTHORITIES.

 PITIS, POLES, MARKER POSTS, SIGNS, ETC. HAVE BEEN PLOTTED ON THE DRAWINGS WHERE SIGHTED AT THE TIME OF SURVEY BUT THE SURVEY NOT DOES INCLUDE INVESTIGATION OR PHYSICAL LOCATION OF UNDERGROUND INFRASTRUCTURE.

 IT IS THE RESPONSIBILITY OF THE CONTRACTOR PRIOR TO ANY DEMOLITION, EXCAVATION OR CONSTRUCTION ACTIVITY ON OR ADJACENT TO THE SITE TO OBTAIN UPDATED SERVICES DIAGRAMS THROUGH A DIAL—BEFORE—YOU—DIG SEARCH AND PHYSICAL SEARCH TO ESTABLISH AND CONFIRM THE EXACT LOCATION/S AND DEPTH/S OF ALL UNDERGROUND SERVICES, PRIOR TO COMMENCEMENT.



NEW CONCRETE FOOTPATH 75mm THICK 25MPa COMPRESSIVE STRENGTH UNREINFORCED PLAIN CONCRETE BROOM FINISH



NEW CONCRETE FOOTPATH 130mm THICK 25MPa COMPRESSIVE STRENGTH REINFORCED WITH SL72 MESH 30 TOP COVER COVE FINISH

LOCALITY PLAN NOT TO SCALE









