

northern beaches council

Pedestrian 'Coast Walk' Connection - Mona Vale Beach

Draft Landscape Concept Plan - For Consultation

15/12/2021 | Scale 1:500 @A3

0 5 10 15 20 25 M

Legend

Pavements

- Existing insitu concrete
- Proposed insitu concrete
- Proposed deco-granite

Walls & Edges

- Sandstone block wall

Furniture & Fittings

- Existing dune protection fence removed
- Proposed dune protection fence
- Reinstate existing memorial picnic tables and seats

Planting

- Proposed turf
- Mulch

Trees

- Trees - retained
- Tree Protection Zone
- Structural Root Zone

Existing Carpark

+ RL 7.45

+ EL 7.45

+ RL 7.45

+ RL 7.30

1:30

1:48

+ RL 7.45

+ RL 7.10

1:37

+ TOW 7.40

+ RL 7.41

+ TOW 7.41

+ RL 7.40

+ TOW 7.38

+ RL 7.38

+ RL 7.36

+ TOW 7.36

+ RL 7.19

+ EL 7.14

+ EL 6.93

+ EL 7.70

Additional bin storage

New concrete pathway connecting Mona Vale SLSC and new amenities block

New concrete path to match finish and colour of new pavement surrounding SLSC and amenities block

Mulched rings around the base of trees with a new deco granite area to protect the root system of existing significant trees

New pathway to ensure smooth transition with finished levels of Mona Vale SLSC development

New pathway to ensure smooth transition with existing ground levels

Mona Vale SLSC Upgrade under construction

Turfed seating terrace

Mona Vale Beach Sand Dune

Mona Vale Beach

northern beaches council

Pedestrian 'Coast Walk' Connection - Mona Vale Beach

Draft Detailed Plan 01 - For Consultation

15/12/2021 | Scale 1:200 @A3

0 2 4 6 8 10 M

Legend

Pavements

- Existing insitu concrete
- Proposed insitu concrete
- Proposed deco-granite

Walls & Edges

- Sandstone block wall

Furniture & Fittings

- Existing dune protection fence removed
- Existing dune protection fence retained
- Proposed dune protection fence
- Reinstate existing memorial picnic tables and seats

Planting

- Existing native groundcovers
- Existing turf
- Proposed turf
- Mulch

Trees

- Trees - retained
- Tree Protection Zone
- Structural Root Zone

New beachfront amenities near completion

Existing Carpark

Mulched rings around the base of trees with a new deco granite area to protect the root system of existing significant trees

Ensure smooth transition between existing ground levels and finished levels of new pathway

2x carparks to be removed to faciliate beach rake and emergency access

New lifeguard facilities near completion

New pathway to ensure smooth transition with existing ground levels. Levels to be confirmed following completion of new amentities block

New concrete path to match finish and colour of new pavement surrounding SLSC and amenities block

Seating edge to support surf watching and beach views

Flush transition between pathway and turf platform to provide equitable access

Additional bin storage

Turfed seating terrace

New pathway to ensure smooth transition with existing ground levels

Mona Vale Beach Sand Dune

Mona Vale Beach

northern beaches council

Pedestrian 'Coast Walk' Connection - Mona Vale Beach

Draft Detailed Plan 02 - For Consultation

15/12/2021 | Scale 1:200 @A3

0 2 4 6 8 10 M



01 Montage - North Facing
Before



02 Montage - North Facing
After



03 Montage - South Facing
Before



04 Montage - South Facing
After

northern beaches council

Pedestrian 'Coast Walk' Connection - Mona Vale Beach

Draft Montages - For Consultation

15/12/2021 | Scale N/A